

## Engineer's Estimate

City of Kingsville  
 GLO SW Project 2  
 N. 19<sup>TH</sup> ST. Storm Water Improvements  
 CDBG-MIT GLO Contract NO. 22-085-009-D237  
 City of Kingsville Bid No. 24-19

Bids are invited for several items and quantities of work as follows:

### 1. Base Bid

ITEM	DESCRIPTION	UNIT	QTY.	UNIT COST	TOTAL
A1	Mobilization / Bonds / Insurance	LS	1	\$	\$
A2	Traffic Control	LS	1	\$	\$
A3	SWPP (Sediment Control Fence)	LF	1819	\$	\$
A4	SWPP (Erosion Control Log)	LF	36	\$	\$
A5	Remove Existing Driveway Asphalt	SY	28	\$	\$
A6	Remove Existing Driveway Gravel	SY	28	\$	\$
A7	Remove Existing 36" RCP	LF	1438	\$	\$
A8	Remove Existing Storm Water Manhole W/ Curb Inlet	EA	1	\$	\$
A9	Remove Existing Headwall	EA	1	\$	\$
A10	Remove Existing Sign	EA	4	\$	\$
A11	Repair Asphalt Driveway	SY	28	\$	\$
A12	Repair Gravel Driveway	SY	28	\$	\$
A13	6' x 4' R.C.B.	LF	1430	\$	\$
A14	24" Ø RCP CL III	LF	7	\$	\$
A15	Utility Adjustment	LS	1	\$	\$
A16	5'x5' Junction Box	EA	1	\$	\$
A17	Curb Inlet	EA	4	\$	\$
A18	Headwall	EA	1	\$	\$
A19	Re-Installing Existing Signs	EA	4	\$	\$

TOTAL BID \$ \_\_\_\_\_  
 ENGINEER'S ESTIMATE \$ \_\_\_\_\_ 1,193,042.50

Juan Carlos "Charlie" Cardenas, P.E.  
 Senior Engineer

