



---

**P. O. BOX 1458 - KINGSVILLE, TEXAS 78364**

**Addendum No. 2**

**CDBG-MIT GLO CONTRACT NO. 22-085-009-D237**

**(CITY OF KINGSVILLE BID NO. 26-04)**

**CITY OF KINGSVILLE GLO SW PROJECT 7 (S. 6TH ST.) STORM WATER IMPROVEMENTS**

The above referenced Bid Opening is modified to provide additional information as follows:

1. Q. Do we need to turn in our SAM certifications, or only after award?  
A. This is typically verified during the awarding process.
  
2. Q. Is Geotech available? With some of those boxes going as deep as they are, I'm wondering if dewatering will be needed.  
A. No Geotech is available for this project.
  
3. Q. What class of RCB/RCP shall be used? In the bidding documents both CL 3 and CL 5 are stated.  
A. General Notes, Section 5 - Utilities and Storm Sewer, Note 3 states "ALL STORM SEWER PIPE SHALL BE CLASS IV REINFORCED CONCRETE PIPE UNDER DRIVEWAYS AND CLASS 5 REINFORCED CONCRETE PIPE UNDER STREET". If not under driveways/roadways, class 3 is acceptable.
  
4. Q. Where is the historical landfill noted? Do you anticipate the location to have any impact on the construction?  
A. The historical location is across US 77 BUS near the railroad. No impact is anticipated, as it is outside the project limits.
  
5. Q. For the 'Utility Adjustment' item... There's really no way to quantify this or the cost before breaking ground. Can this be made an allowance?  
A. Please refer to General Notes, Section 1, Note 35.
  
6. Q. Will PCMB be required? They were not mentioned In any of the TCP plan sheets, but I want to make sure.  
A. The project is being bid and awarded contingent on pending TxDot approval. At this time, PCMB is not required.



---

**P. O. BOX 1458 - KINGSVILLE, TEXAS 78364**

7. Q. The first line of the alternate section of the bid form has A24, which is a reduction. Should this be part of the alternate or base bid?  
A. This reduction is part of the additive bid. In the event the additive bid is awarded, it will not be required from the base bid award.
  
8. Q. Can you please provide an outfall detail, or is it just the scored RCP and riprap shown in the plans?  
A. Addendum #1, sheets C35, TxDot FW-0 shows the detail for outfall structures.
  
9. Q. Will the newly installed storm sewer utilities (RCB/RCP) be required to be CCTV.  
A. No, the installed RCB/RCP are not required to be CCTV.
  
10. Q. Is item A34 1 LS or 1 EA? I can only find one sign unless you intend on more.  
A. This is a LS item for completion of the project. In the event there are more than shown on the plans, it remains LS. This is a labor-only item as existing signs shall be removed and relocated.

Note: To comply with the Instruction to **Bidders paragraph 2**, no other addendum will be issued after today.

A signed copy of this Addendum No. 2 must accompany each proposal submission. In doing so, the Proposer acknowledges receipt of this Addendum No. 2, and agrees if selected as the successful Proposer, to be bound by the terms as amended. All terms of Bid No. 26-04 which are not amended hereby, remain in full force and effect.

Questions concerning this Addendum No. 2 should be addressed to City Engineer, Juan Carlos Cardenas, P.E. via email to [ccardenas@cityofkingsville.com](mailto:ccardenas@cityofkingsville.com).

\_\_\_\_\_  
Juan Carlos Cardenas, P.E., City Engineer

\_\_\_\_\_  
Date

---

**Acknowledgement of Addendum No. 2:**

By: \_\_\_\_\_ Title: \_\_\_\_\_

Signed: \_\_\_\_\_